



Door & Window Schedule		Bottom EL.	Qty
<b>Walk Doors Frame Outs</b>			
D1	4' max width FO		8
D2	4' to 7' width FO		8
<b>Window Frame Outs</b>			
W1	2'-11 1/2" x 6'-1 1/4" FO		7
W2	4' x 6' FO		9
W3	4' x 7'-4" FO		5
W4	5' x 7'-4" FO		6
W5	12' x 9' FO		2
W6	16' x 9' FO		1
All interior doors by others			

All interior doors not labeled to be provided & framed by Non Wick Contractor.

Church Refer to Cover page for Dimensions	25 PSF Balanced Roof Load 90 MPH Wind Load (3 sec gust) 2000 PSF Presumptive Soil Bearing	 <b>Wick Buildings</b> <sup>®</sup>	Engineering Office: 405 Walter Road, Mazomanie, Wisconsin 53560 Phone: 608-795-2294 Fax: 608-795-2534	<b>First Church of God</b>		
				<b>Floor Plan-Door &amp; Window Schedule</b>		
				Drawn By:MD	Job No.: 071137E	View: Floor_doors
				Scale:240	Scale = 1'=20'	Page: 4
			Rev. Date:	Org. Date:11-12-07	File: G:\...071137.dwg	